

Test Certificate

Lot 242 Russell Road East, Munster WA 6166 PO Box 38, Hamilton Hill WA 6963 T: +61 8 9411 1000 F: +61 8 9411 1150

Final

Product Certified: Ground Granulated Blast Furnace Slag

Test Certificate Number: 190092

Despatched From: Cockburn Cement, Port Hedland Plant, WA

 Sample Code:
 B0696b7

 Sample Date:
 6/12/2018

| Nominal Blend | Requirements | Result |
|-------------------------------------------|--------------|--------|
| Ground Granulated Iron Blast-Furnace Slag | | >95 % |
| Calcium Sulphate | | <5 % |

| Reportable Property | Test Method | Requirements of | Result |
|---------------------------------------------|-------------|-----------------|--------------|
| | | AS3582.2 | |
| Alumina (Al ₂ O ₃) | AS2350.2 | Max 18.0 % | 17.2 % |
| Total Iron (FeO) | AS2350.2 | N/R | 0.4 % |
| Magnesia (MgO) | AS2350.2 | Max 15.0 % | 10.8 % |
| Total Alkali (Na ₂ O Equivalent) | AS2350.2 | N/R | 0.6 % |
| Manganese (MnO) | ASTM C114 | N/R | 0.6 % |
| Sulfate (as SO ₃) content | AS3583.8 | N/R | 0.5 % |
| Sulfide Sulfur (S) | AS3583.7 | Max 1.5 % | 0.7 % |
| Chloride Ion Content | AS3583.13 | Max 0.1 % | 0.006 % |
| Loss on Ignition | AS3583.3 | N/R | -0.9 % |
| Insoluble Residue | AS3583.14 | N/R | 0.1 % |
| 45 μm Residue | AS3583.1 | N/R | 97 % passing |
| Relative Density | AS3583.5 | N/R | 2.91 |
| Relative Water Requirement | AS3583.6 | N/R | 99 % |
| Strength Index | AS3583.6 | N/R | 104 % |
| Other Properties | | | |
| SiO ₂ | AS2350.2 | N/R | 31.1 % |
| CaO | AS2350.2 | N/R | 36.7 % |
| Fineness Index | AS2350.8 | N/R | 415 m²/kg |

This document shall not be reproduced except in full.

REMARKS

These test results apply specifically to the above designated sample as received at the Adelaide Brighton Cement Birkenhead Laboratory (Accredited number: 252), 62 Elder Rd Birkenhead SA 5015.

For Relative Water and Strength Index testing the reference control used is Birkenhead GP code B069db0.

This despatch grab sample complies to the requirements of AS3582.2:2016, Ground Granulated Blast Furnace Slag. N/R = No Requirement



Accredited for compliance with ISO/IEC 17025 - Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Approved Signatory

F. Pope Issue Date: 11/02/2019