

Cement Test Certificate

Lot 242 Russell Road East, Munster WA 6166 PO Box 38, Hamilton Hill WA 6963 T: +61 8 9411 1000 F: +61 8 9411 1150 Type GP General Purpose Cement

Final

Product Cartified

ABN 50 006 673 470

	Test Certificate Number: Produced At: Sample Code:	180605 Cockburn Cement, Munster Plant, WA B0641e2	
	Sample Date:	28/05/2018	
Nominal Blend		Requirements	Result
Clinker			>86.5 %
Ground Granulated Iron Blast-Furnace Slag			Nil
Mineral Addition		Max 7.5 %	<7.5 %
Calcium Sulphate			<5 %
Minor Additional Constituents		Max 5 %	Nil
		Requirements of	

Reportable Property	rty Test Method	Requirements of	Result	
Reportable Froperty	restimethod	AS3972	nesun	
3 Day Strength	A\$2350.11	N/R	41.6 MPa	
7 Day Strength	AS2350.11	Min 35.0 MPa	51.9 MPa	
28 Day Strength	AS2350.11	Min 45.0 MPa	67.0 MPa	
Initial Set Time	AS2350.4	Min 45 min	120 min	
Final Set Time	AS2350.4	Max 360 min	210 min	
Soundness	AS2350.5	Max 5 mm	1 mm	
Sulfuric Anhydride content (SO ₃)	AS2350.2	Max 3.5 %	3.3 %	
Chloride Ion	BH-TM-0507	Max 0.10 %	0.018 %	
Other Properties				
SiO ₂	AS2350.2	N/R	18.7 %	
Al ₂ O ₃	AS2350.2	N/R	5.0 %	
Fe ₂ O ₃	AS2350.2	N/R	2.8 %	
CaO	AS2350.2	N/R	62.6 %	
MgO	AS2350.2	N/R	1.6 %	
Na₂O Equivalent	AS2350.2	N/R	0.6 %	
Loss on Ignition	AS2350.2	N/R	4.3 %	
Fineness Index	AS2350.8	N/R	415 m²/kg	
Normal Consistency	AS2350.3	N/R	28.0 %	

This document shall not be reproduced except in full.

REMARKS

These test result apply specifically to the sample as received at the Adelaide Brighton Cement Birkenhead Laboratory (Accreditation number: 252), 62 Elder Rd Birkenhead SA 5015.

This despatch grab sample complies to the requirements of AS3972:2010, Type GP Cement. N/R = No Requirement



Accredited for compliance with ISO/IEC 17025 - Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Marchite

Approved Signatory M. Wythe

Issue Date:

5/07/2018