

Cement Test Certificate

Lot 242 Russell Road East, Munster WA 6166 PO Box 38, Hamilton Hill WA 6963 T: +61 8 9411 1000 F: +61 8 9411 1150 Type GP General Purpose Cement

Final

ABN 50 006 673 470

Papartabla		Mathad	Requirements of	Pocult	
Minor Additional Constituents			Max 5 %	Nil	
Calcium Sulphate				<5 %	
Mineral Addition			Max 7.5 %	<7.5 %	
Ground Granulated Iron Blast-Furna	ace Slag			Nil	
Clinker				>86.5 %	
Nominal B	lend		Requirements		
	Sample Date:	5/11/2019			
	Produced At: Sample Code:	Cockburn Cement, Munster Plant, WA B07227f			
Test Certificate Number:	190545				
	Product Certified:		Type GP General Purpose Cement		

Reportable Property	Test Method	Requirements of	Result	
Reportable Property		AS3972	Result	
3 Day Strength	AS2350.11	N/R	39.8 MPa	
7 Day Strength	AS2350.11	Min 35.0 MPa	50.9 MPa	
28 Day Strength	AS2350.11	Min 45.0 MPa	64.0 MPa	
Initial Set Time	AS2350.4	Min 45 min	150 min	
Final Set Time	AS2350.4	Max 360 min	195 min	
Soundness	AS2350.5	Max 5 mm	1 mm	
Sulfuric Anhydride content (SO ₃)	AS2350.2	Max 3.5 %	3.3 %	
Chloride Ion	BH-TM-0507	Max 0.10 %	0.012 %	
Other Properties				
SiO ₂	AS2350.2	N/R	19.1 %	
Al ₂ O ₃	AS2350.2	N/R	5.1 %	
Fe ₂ O ₃	AS2350.2	N/R	2.7 %	
CaO	AS2350.2	N/R	62.6 %	
MgO	AS2350.2	N/R	1.4 %	
Na ₂ O Equivalent	AS2350.2	N/R	0.5 %	
Loss on Ignition	AS2350.2	N/R	4.7 %	
Fineness Index	AS2350.8	N/R	405 m²/kg	
Normal Consistency	AS2350.3	N/R	28.0 %	

This document shall not be reproduced except in full.

REMARKS

These test result apply specifically to the sample as received at the Adelaide Brighton Cement Birkenhead Laboratory (Accreditation number: 252), 62 Elder Rd Birkenhead SA 5015.

This despatch grab sample complies to the requirements of AS3972:2010, Type GP Cement. N/R = No Requirement



Accredited for compliance with ISO/IEC 17025 - Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Approved Signatory F. Pope

Issue Date:

10/12/2019